

HINDUSTAN PETROLEUM CORPORATION LIMITED

(A Government of India Enterprise)

QUALITY CONTROL LABORATORY

MAZGAON TERMINAL

LUBE PLANT, HAY BUNDER ROAD, MAZGAON

MUMBAI,400033

LABORATORY TEST REPORT**SEETUL N 68 (P) (1X210L)(2317241)**

Laboratory Serial No.	PP 945	Sample Drawn By	QC OFFICER
JDE Serial No	1188138	Date Sample Drawn	10/10/22
Batch No / Lot No	M1-22-K-484	Date Received In Lab	10/10/22
Work Order No	985437	Date Tested	10/10/22
Tank /Kettle/Location	WHS	Particular of Sample	DRUM
Plant Code/ Name		Sampling Plan	IS 1447

Test Line Number	Test Description/ Characteristics	Units	Test Method	Specifications		Result Value
				Min	Max	
1	SEETUL N 68 (P) APPEARANCE	.	0	B&C	B&C	B&C
2	SEETUL N 68 (P)COPSTRIPCOR@100	.	P 15 D 130 IP 154	-	1	1
3	SEETUL N 68 (P) DENSITY @ 29.5	gm/cc	P 16 D 1298 IP 160	-	-	.8533
4	SEETUL N 68 (P) DIELETRIC STR	.	D 877 IP 295	20	-	26
5	SEETUL N 68 FLASH POINT	°C	P 69 D 92 IP 36	210	-	264
6	SEETUL N 68 (P) KV @ 40	cSt	P 25 D 445 IP 71	65.00	73.00	68.94
7	SEETUL N 68 (P) MOISTURE	Parts Per Million	D 1744	-	100	0
8	SEETUL N (P) NEUT NO.	mg KOH/g	P 2 D 974 IP 139	-	.05	.03
9	SEETUL N 68 (P) POUR POINT	deg.C	P 10 D 97 IP 15	-	-27	-30
10	SEETUL N 68 (P) VI	.		100	-	113

Remarks : Sample meets the specification in above tests.

Note:

- 1) The report refers only to the sample tested.
- 2) The test report shall not be reproduced except in full without prior written approval of the Lab Incharge.
- 3) This test report shall not be used in any advertising media or as evidence in the Court of Law without prior written consent of Laboratory.
- 4) Test results reported are valid at the time of testing
- 5) This is a system generated test report and hence does not require signature.

Reviewed and Authorized by: