



BHARAT PETROLEUM CORPORATION LIMITED
(A Govt. of India Enterprise)
WADILUBE INSTALLATION
Mallet Road, Wadibunder, Mumbai – 400 009
(An ISO/IEC 17025:2017, ISO 9001:2015; ISO 14001:2015; ISO 50001:2018;
ISO 45001:2018 Certified)



QUALITY ASSURANCE LABORATORY

TEST REPORT

Test Report No. : 23-56239229
Issued To : Plant Manager / Customer Date : 27.11.2023
Name of Product : **MAK SCREWCOM** Date of Sampling : 25.11.2023
Batch Number : W.56239229 Date of Receipt in Lab : 25.11.2023
Reason for Testing : Batch Formation Date of Testing : 25.11.2023

S. No.	Characteristic	Test Method	Test Results
1.	Appearance	Visual, SOP-09	Clear
2.	Color	ASTM D1500	L 0.5 ASTM Color
3.	Crackle	SOP-10	Negative
4.	Density at 29.5 °C, g/ml	ASTM D4052	0.8470
5.	Kinematic Viscosity at 40 °C, cSt	ASTM D445	61.88
6.	Pour Point, °C	ASTM D5949	-21
7.	Water Separability Characteristic at 54 °C	ASTM D1401	40-40-0 (15)
8.	Foaming Tendency / Stability, volume of foam after 10 minutes, ml, Max a) at 24 °C b) at 93.5 °C c) at 24 °C after the cooling down from 93.5 °C	ASTM D892	Nil / Nil Nil / Nil Nil / Nil

Remark:

- 1. The Product as represented by the sample meets the specification of MAK SCREWCOM w.r.t. the above tests carried out as per Internal Specification.**

Authorised Signatory

(Kishore Dhale)

Notes:

1. The sample is drawn by the client & the result relates to the sample tested.
2. This certificate shall not be reproduced wholly or in part without prior written consent of the laboratory
3. This certificate shall not be used in any advertising media or as evidence in the court of Law without prior written consent of laboratory
4. Latest version of test methods used as per latest specification.

*** End of Test Report ***